

GPS #: 4435

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/C-5

City / Location: San Juan Capistrano

Scale Factor: 0.99995721

Ellipsoid Red. Factor: 0.99999043

Combination Factor: 0.99994763

Convergence Angle: -00 46 45.59372

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 33.80578	117 40 05.55776	2119785.134	6129219.077	200.065
2007.00	33 28 33.82267	117 40 05.57381	2119786.86	6129217.74	

References: RSB 103/8-12, RSB 151/1-11

Description:

FD PUNCHED LARGE ROUND HEAD SPIKE AND WASHER, STAMPED "LS 4279 ", FLUSH. STATION IS LOCATED FROM THE INTER OF LA NOVIA AVE. AND VALLE RD., PROCEED SW'LY ON VALLE RD. 0.55 MILE TO BOTTOM OF HILL- VALLE RD. TURNS INTO FORSTER RANCH RD.-UPHILL ON FORSTER RANCH RD. 0.6 MILE TO THE MONUMENT LOCATED ALONG THE APPARENT CENTERLINE OF FORSTER RANCH RD.

