

GPS #: 4436R1

Date Destroyed:

Date Revised: 1/29/2004

Benchmark Designation:

OCS Index Map: **6LB**

Page/Grid: 972/C-6

City / Location: San Juan Capistrano

Scale Factor: 0.99995687

Ellipsoid Red. Factor: 0.99999724

Combination Factor: 0.99995411

Convergence Angle: -00 46 45.09108

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 04.92364	117 40 04.64306	2116865.081	6129256.849	
2007.00	33 28 04.94057	117 40 04.65902	2116866.81	6129255.52	

References: RSB 151/1-11, CR 2002-2021

Description:

FD SPIKE AND 1 1/2" TAG STAMPED "CALTRANS".
MONUMENT WAS RESET PER CORNER RECORD #
2002-2021 IN LIEU OF GEAR SPIKE WITH WASHER,
STAMPED "LS 3419", FLUSH. STATION IS LOCATED
AT APPARENT CENTERLINE INTER OF CAMINO LAS
RAMBLAS AND SAN DIEGO FREEWAY <5> ON/OFF
RAMPS, NE'LY 200'+/- FROM FREEWAY OVERPASS.

