

GPS #: 4526

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/C-2

City / Location: Coto De Caza

Scale Factor: 0.99996863

Ellipsoid Red. Factor: 0.99995276

Combination Factor: 0.99992139

Convergence Angle: -00 43 47.40138

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 34.26471	117 34 41.28726	2180111.217	6157456.770	987.147
2007.00	33 38 34.28149	117 34 41.30242	2180112.93	6157455.51	

References: PMB 244/1-3, RSB 151/1-11

Description:

FD GEAR SPIKE AND BRASS WASHER STAMPED "RCE 23956" FLUSH IN A.C. SURFACE, AT THE CENTERLINE INTER OF PLANO TRABUCO RD. AND DOVE CANYON DR.

