

GPS #: **4532**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 892/G-6

City / Location: Rancho Santa Margarita

Scale Factor: 0.99996637

Ellipsoid Red. Factor: 0.99996758

Combination Factor: 0.99993395

Convergence Angle: -00 45 13.96677

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 03.91368	117 37 18.81704	2171151.855	6144019.802	677.492
2007.00	33 37 03.93057	117 37 18.83271	2171153.58	6144018.50	

References: A/6-7 2559, RSB 151/1-11

Description:

FD 2" BRASS DISK STAMPED "LS 3246" DOWN 1.2' IN O.C.S. WELL MONUMENT, LOCATED AT THE CENTERLINE E.C. ALONG ARROYO VISTA, 0.1+/- MILE S'LY FROM ITS INTER WITH PARAISO.

