

GPS #: 4542

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 923/C-2

City / Location: Coto De Caza

Scale Factor: 0.99996462

Ellipsoid Red. Factor: 0.99997364

Combination Factor: 0.99993827

Convergence Angle: -00 44 05.08373

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 48.22886	117 35 13.46520	2163364.682	6154521.385	550.790
2007.00	33 35 48.24578	117 35 13.48102	2163366.41	6154520.07	

References: MM 655/1-28, RSB 151/1-11

Description:

FD PUNCHED SPIKE WITH 1 3/8" BRASS TAG
STAMPED "LS 4965" FLUSH IN A.C., LOCATED AT
THE CENTERLINE "T" INTER OF COTO DE CAZA DR.
AND POLO.

