

GPS #: **4547**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/C-7

City / Location: Coto De Caza

Scale Factor: 0.99996561

Ellipsoid Red. Factor: 0.99996980

Combination Factor: 0.99993541

Convergence Angle: -00 44 04.09977

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 31.89111	117 35 11.67463	2167775.681	6154729.406	631.226
2007.00	33 36 31.90794	117 35 11.69032	2167777.40	6154728.10	

References: MM 567/31-35, RSB 151/1-11

Description:

FD PUNCHED SPIKE WITH 1 3/8" BRASS TAG
STAMPED "LS 4965" FLUSH IN A.C., LOCATED
ALONG THE CENTERLINE OF COTO DE CAZA DR.,
9.91' S'LY FROM ITS CENTERLINE INTER WITH
FAIRWAY LN.

