

GPS #: 4549R1

Date Destroyed:

Date Revised: 6/7/2001

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/D-5

City / Location: Coto De Caza

Scale Factor: 0.99996697

Ellipsoid Red. Factor: 0.99996158

Combination Factor: 0.99992854

Convergence Angle: -00 43 40.03013

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 28.63357	117 34 27.87322	2173463.396	6158506.469	
2007.00	33 37 28.65036	117 34 27.88871	2173465.11	6158505.18	

References: RSB 151/1-11, CR 2001-1062

Description:

FD PUNCHED SPIKE AND 1 1/4" OCS BRASS WASHER STAMPED "4549R1 5-01", FLUSH, IN LIEU OF RAIL-ROAD SPIKE WITH "+" ON TOP. MONUMENT WAS RESET PER CORNER RECORD # 2001-1062. MONUMENT IS LOCATED AT THE VISUAL CENTERLINE INTER OF VIA PARDAL AND VIA GALLO.

