

GPS #: 4550

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/C-6

City / Location: Coto De Caza

Scale Factor: 0.99996658

Ellipsoid Red. Factor: 0.99996647

Combination Factor: 0.99993305

Convergence Angle: -00 43 57.26011

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 12.48483	117 34 59.22794	2171865.023	6155834.460	700.671
2007.00	33 37 12.50164	117 34 59.24358	2171866.74	6155833.16	

References: MM 573/39-43, RSB 151/1-11

Description:

FD PUNCHED SPIKE WITH 1 3/8" BRASS TAG STAMPED "LS 4965" FLUSH IN A.C., LOCATED ALONG THE CENTERLINE OF VISTA DEL VERDE, 0.1 +/- MILE S'LY FROM ITS INTER WITH VIA PAJARO, AT THE B.C.

