

GPS #: 4555

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/C-3

City / Location: Coto De Caza

Scale Factor: 0.99996797

Ellipsoid Red. Factor: 0.99995760

Combination Factor: 0.99992557

Convergence Angle: -00 44 03.69538

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 08.56470	117 35 10.93872	2177545.727	6154916.880	886.081
2007.00	33 38 08.58160	117 35 10.95411	2177547.45	6154915.60	

References: MM 595/10-15, RSB 151/1-11

Description:

FD PUNCHED SPIKE WITH 1 3/4" ALUMINUM TAG STAMPED "LS 3246" FLUSH IN A.C., AT THE CENTERLINE INTER OF COTO DE CAZA DR. AND PLANO TRABUCO RD.

