

GPS #: **4556R1**

Date Destroyed:

Date Revised: 2/2/2010

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 893/C-4

City / Location: Coto De Caza

Scale Factor: 0.99996765

Ellipsoid Red. Factor: 0.99995757

Combination Factor: 0.99992522

Convergence Angle: -00 44 02.28828

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 56.06569	117 35 08.37811	2176279.666	6155117.175	
2007.00	33 37 56.08257	117 35 08.39357	2176281.39	6155115.89	

References: MM 432/21-38, RSB 151/1-11, CR 2009-2742, CR 2009-3436

Description:

FD GEAR SPIKE AND TAG STAMPED "LS 5411", FLUSH, IN LIEU OF PUNCHED SPIKE WITH 1 3/4" BRASS TAG STAMPED "LS 3109" FLUSH IN A.C., AT THE CENTERLINE INTER OF TRIGO TRAIL AND MANDARINA LN.

