

GPS #: 4569

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 862/J-5

City / Location: Trabuco Canyon

Scale Factor: 0.99997148

Ellipsoid Red. Factor: 0.99994349

Combination Factor: 0.99991497

Convergence Angle: -00 44 46.17702

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 18.65336	117 36 28.24584	2190778.358	6148552.407	1180.965
2007.00	33 40 18.67002	117 36 28.26135	2190780.06	6148551.12	

References: RSB 98/4, RSB 151/1-11

Description:

FD 3 1/4" BRASS O.C.S. DISK STAMPED "4/3/9/10 T6S R7W" DOWN 1.7' IN O.C.S. WELL MONUMENT, LOCATED, FROM THE ENTRANCE TO THE RAMAKRISHNA MONASTERY OFF LIVE OAK CANYON RD., PROCEED UPHILL 0.35 MILE TO SAID WELL MONUMENT, LOCATED ALONG A.C. RD. 57'+/- BEFORE WOODEN FENCE ENTRANCE TO SAID MONASTERY.

