

**GPS #:** 4661

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/A-6

City / Location: Irvine

Scale Factor: 0.99996696

Ellipsoid Red. Factor: 0.99998542

Combination Factor: 0.99995238

Convergence Angle: -00 52 09.01793

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 28.40240	117 49 54.11802	2174531.515	6080190.540	306.646
2007.00	33 37 28.41875	117 49 54.13488	2174533.19	6080189.14	

References: OCS FILE # IW94/5-51N, GEODETIC UNIT

## Description:

FD 3 1/4" ALUMINUM OCS DISK STAMPED "COYOTE 3", SET IN 8" DIA. CONC. COLLAR, FLUSH IN GROUND, LOCATED FROM THE SOUTHBOUND SAN JOAQUIN TRANSPORTATION CORRIDOR FROM BONITA CANYON RD., PROCEED S'LY ALONG CORRIDOR 0.5 +/- MILES TO THE LARGE "NEWPORT COAST DR" OFFRAMP SIGN. STATION IS LOCATED 250' +/- SW'LY ON SW'LY SIDE AND ON TOP OF HILL.

