

**GPS #:** 4671

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/B-7

City / Location: Unin., Orange County

Scale Factor: 0.99996606

Ellipsoid Red. Factor: 0.99997715

Combination Factor: 0.99994321

Convergence Angle: -00 52 02.53194

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 50.81208	117 49 42.31496	2170717.247	6081130.975	479.392
2007.00	33 36 50.82851	117 49 42.33211	2170718.93	6081129.55	

References: OCS FILE # IW94/5-51N, GEODETIC UNIT

### Description:

FD 2" I.P. WITH 1 3/8" BRASS OCS TAG STAMPED "WEATHER AUX 2 RESET 1995" UP 0.2', LOCATED FROM THE "T" INTER OF NEWPORT COAST DR. AND THE A.C. RD. TO THE METHANE TREATMENT PLANT, MONUMENT IS LOCATED SW'LY 500' +/- ON SMALL KNOLL WHICH CONTAINS OLDER VEGETATION.

