

GPS #: 4736

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 861/G-3

City / Location: Unin., Orange County

Scale Factor: 0.99997347

Ellipsoid Red. Factor: 0.99997189

Combination Factor: 0.99994536

Convergence Angle: -00 47 48.07947

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 26.63998	117 41 59.26793	2198026.456	6120674.447	589.398
2007.00	33 41 26.65645	117 41 59.28392	2198028.14	6120673.12	

References: OCS SURVEY FILE # R92-10A

Description:

FD 6" X 8" CHARRED REDWOOD POST, UP 0.8', WITH PK NAIL AND 2" OCS WASHER STAMPED "1/4 COR 153 9-91". LOCATED IN A NE'LY DIRECTION FROM THE INTER OF IRVINE BLVD. AND "N" ST.; SET 30' DOWN FROM TOP OF RIDGE OFF A DIRT RD.

