

**GPS #:** **4926**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/H-6

City / Location: Surfside

Scale Factor: 0.99997806

Ellipsoid Red. Factor: 1.00000490

Combination Factor: 0.99998298

Convergence Angle: -01 00 29.56080

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 51.19525	118 05 04.99492	2214480.144	6003857.976	-101.348
2007.00	33 43 51.21167	118 05 05.01216	2214481.83	6003856.55	

References: OCS SURVEY FILE # H93/94-15N

**Description:**

FD 2" I.P. WITH 2 1/2" PUNCHED BRASS DISK STAMPED "CCSTWS 11 OCS" FLUSH IN DIRT - LOCATED FROM THE MAIN ENTRANCE TO SURFSIDE COLONY ALONG PACIFIC COAST HWY., PROCEED NW'LY PARALLEL WITH PACIFIC COAST HWY. ALONG DIRT MAINTENANCE RD. 1000'+/- TO A POINT 200'+/- SE'LY OF ANAHEIM BAY SHORELINE, PARK HERE. STATION IS LOCATED 20'+/- SW'LY OF CONC. RETAINING WALL NEAR EDGE OF DIRT RD.

