

GPS #: 4927

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/H-6

City / Location: Surfside

Scale Factor: 0.99997793

Ellipsoid Red. Factor: 1.00000490

Combination Factor: 0.99998289

Convergence Angle: -01 00 28.72092

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 47.22340	118 05 03.46653	2214076.454	6003979.976	-102.096
2007.00	33 43 47.23982	118 05 03.48365	2214078.14	6003978.56	

References: OCS SURVEY FILE # H93/94-15N

Description:

FD 2" I.P. WITH 2 1/2" PUNCHED BRASS DISK
STAMPED "CCSTWS RM 11 OCS" FLUSH IN DIRT -
LOCATED FROM THE MAIN ENTRANCE TO SURFSIDE
COLONY ALONG PACIFIC COAST HWY., PROCEED
NW'LY PARALLEL WITH PACIFIC COAST HWY.
ALONG DIRT MAINTENANCE RD. 500'+/- TO A POINT
600'+/- SE'LY OF ANAHEIM BAY SHORELINE, PARK
HERE. STATION IS LOCATED 20'+/- SW'LY OF TOE OF
SMALL SLOPE NEAR EDGE OF DIRT RD.

