

GPS #: 5000

Date Destroyed:

Date Revised: 2/2/2010

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/J-2

City / Location: Seal Beach

Scale Factor: 0.99998163

Ellipsoid Red. Factor: 1.00000503

Combination Factor: 0.99998666

Convergence Angle: -01 00 06.48971

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 45 33.85876	118 04 23.01065	2224793.805	6007584.730	-105.000
2007.00	33 45 33.87508	118 04 23.02782	2224795.48	6007583.31	

References: A/5-11&12 438, RSB 150/1-9, CR 2009-1971, CR 2009-3102.

Description:

FD 3 3/4" O.C.S. ALUMINUM DISK IN 1.0' CONC. CYLINDER, STAMPED "5-11-7 MARCH 1974". STATION IS LOCATED ON SOUTH SIDE OF WESTMINSTER AVE., 0.25 MILE EAST OF SEAL BEACH BLVD.

