

GPS #: 5003R2

Date Destroyed:

Date Revised: 5/5/2008

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/D-4

City / Location: Huntington Beach

Scale Factor: 0.99996818

Ellipsoid Red. Factor: 1.00000522

Combination Factor: 0.99997339

Convergence Angle: -00 56 26.00200

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 16.83690	117 57 41.77197	2180051.066	6040731.022	
2007.00	33 38 16.85344	117 57 41.78876	2180052.76	6040729.63	

References: MM 303/8-13, RSB 150/1-9, CR 2002-1867, CR 2004-1800, CR 2005-0847

Description:

FD PK WITH TAG STAMPED "LS 5411", FLUSH IN AC, PER CR #2005-0847 IN LIEU OF BRASS PIN AND OCS TAG, FLUSH IN CONC. MONUMENT WAS RESET PER CORNER RECORD # 2002-1867 IN LIEU OF PUNCHED SPIKE, DOWN 0.1' IN CONC. STATION IS LOCATED AT CENTERLINE INTER OF BUSHARD ST. AND BROOKHURST ST.

