

GPS #: 5004R1

Date Destroyed:

Date Revised: 3/29/2006

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/E-3

City / Location: Huntington Beach

Scale Factor: 0.99996867

Ellipsoid Red. Factor: 1.00000517

Combination Factor: 0.99997384

Convergence Angle: -00 56 16.33577

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 35.90432	117 57 24.18158	2181953.750	6042249.582	
2007.00	33 38 35.92093	117 57 24.19838	2181955.45	6042248.19	

References: RSB 150/1-9, CR 2004-1801, CR 2005-1042

Description:

FD MAG NAIL AND WASHER STAMPED "LS 5411" FLUSH, IN LIEU OF FD PUNCHED SPIKE WITH 1 1/2" BRASS TAG, STAMPED "OCS CONTROL POINT". MONUMENT WAS RESET PER CORNER RECORD #2005-1042. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF BROOKHURST ST. AND BANNING AVE.

