

GPS #: 5005R1

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/D-3

City / Location: Huntington Beach

Scale Factor: 0.99996867

Ellipsoid Red. Factor: 1.00000523

Combination Factor: 0.99997390

Convergence Angle: -00 56 27.09095

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 35.79248	117 57 43.75363	2181969.573	6040594.963	
2007.00	33 38 35.80905	117 57 43.77044	2181971.27	6040593.57	

References: MM 303/8-13, RSB 150/1-9, CR 2004-0407, CR 2005-0497

Description:

FD SURVEY MARK SPIKE WITH OCS TAG STAMPED "GPS 5005R1" FLUSH, IN LIEU OF 2" I.P. WITH TACK AND BRASS TAG IN CONC., (ILLEGIBLE), DOWN 0.92' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2005-0497. STATION IS LOCATED AT CENTERLINE INTER OF BUSHARD ST. AND BANNING AVE.

