

GPS #: 5006R1

Date Destroyed:

Date Revised: 9/1/2011

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/C-3

City / Location: Huntington Beach

Scale Factor: 0.99996868

Ellipsoid Red. Factor: 1.00000517

Combination Factor: 0.99997385

Convergence Angle: -00 56 44.99293

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 36.14778	117 58 16.33127	2182050.826	6037841.756	-108.113
2007.00	33 38 36.16422	117 58 16.34810	2182052.51	6037840.36	

References: RSB 150/1-9, CR 2002-1868, CR 2010-0901, CR 2011-1507

Description:

FD NAIL AND TAG STAMPED "LS 5411" IN CONCRETE, DOWN 1.0' IN WELL MONUMENT, IN LIEU OF PUNCHED SPIKE AND WASHER. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF MAGNOLIA ST. AND BANNING AVE.

