

GPS #: 5015R1

Date Destroyed:

Date Revised: 6/10/2008

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/D-1

City / Location: Huntington Beach

Scale Factor: 0.99997006

Ellipsoid Red. Factor: 1.00000510

Combination Factor: 0.99997516

Convergence Angle: -00 56 27.47085

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 28.02669	117 57 44.44498	2187249.625	6040623.230	
2007.00	33 39 28.04322	117 57 44.46186	2187251.32	6040621.83	

References: RSB 108/49-50, RSB 150/1-9, CR 2004-0414, CR 2005-1037, CR 2008-0178

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5662 FLUSH, IN LIEU OF PUNCHED RAILRD. SPIKE, DOWN 0.1'. MONUMENT WAS RESET PER CORNER RECORD #2005-1037. STATION IS LOCATED AT CENTERLINE INTER OF BUSHARD ST. AND ATLANTA AVE.

