

GPS #: 5017

Date Destroyed:
Date Revised: 8/26/1999
Benchmark Designation:
OCS Index Map: 4LB
Page/Grid: 888/B-1
City / Location: Huntington Beach

Scale Factor: 0.99997005
Ellipsoid Red. Factor: 1.00000530
Combination Factor: 0.99997535
Convergence Angle: -00 57 01.81969

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 27.61597	117 58 46.95222	2187295.323	6035339.662	-110.725
2007.00	33 39 27.63242	117 58 46.96913	2187297.01	6035338.26	

References: MM 334/35-37, RSB 150/1-9, CR 2003-1276

Description:

FD 2" I.P. WITH BRASS TAG STAMPED "OCS BM" IN LIEU OF 2" I.P. TAGGED "OCSD BM", DOWN 0.27' IN WELL MONUMENT. ACCEPTED AS CENTERLINE INTERSECTION. STATION IS LOCATED AT CENTERLINE INTER OF NEWLAND ST. AND ATLANTA AVE.

