

GPS #: 5018

Date Destroyed:

Date Revised: 8/3/2000

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 888/A-1

City / Location: Huntington Beach

Scale Factor: 0.99997005

Ellipsoid Red. Factor: 1.00000525

Combination Factor: 0.99997530

Convergence Angle: -00 57 18.99454

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 27.44353	117 59 18.20664	2187321.829	6032697.866	-109.796
2007.00	33 39 27.45990	117 59 18.22349	2187323.51	6032696.47	

References: PMB 214/39-41, RSB 150/1-9

Description:

FD BRASS TAG IN CONC. IN HUNTINGTON BEACH WELL MONUMENT. STATION IS LOCATED 20.00' WEST OF THE CENTERLINE OF BEACH BLVD AND ALONG THE CENTERLINE OF ATLANTA AVE. MONUMENT IS THE SOUTHWEST CORNER OF SECTION 12, TOWNSHIP 6 SOUTH AND RANGE 11 WEST.

