

**GPS #:** 5023

Date Destroyed:

Date Revised: 3/29/2006

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/A-7

City / Location: Huntington Beach

Scale Factor: 0.99997077

Ellipsoid Red. Factor: 1.00000463

Combination Factor: 0.99997541

Convergence Angle: -00 57 19.23851

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 53.75439	117 59 18.65061	2189981.581	6032704.686	-96.837
2007.00	33 39 53.77085	117 59 18.66745	2189983.27	6032703.29	

References: PMB 35/26, RSB 150/1-9

## Description:

FD 2" I.P. WITH BRASS TAG STAMPED "CITY OF HB RCE 10655", DOWN 0.6' IN WELL MONUMENT. STATION IS LOCATED ALONG THE CENTERLINE OF INDIANAPOLIS AVE., 20.00' W'LY FROM ITS CENTERLINE INTER WITH BEACH BLVD., IN THE CITY OF HUNTINGTON BEACH.

