

GPS #: 5024R1

Date Destroyed:

Date Revised: 6/10/2014

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/B-7

City / Location: Huntington Beach

Scale Factor: 0.99997078

Ellipsoid Red. Factor: 1.00000524

Combination Factor: 0.99997601

Convergence Angle: -00 57 02.02875

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 53.84014	117 58 47.33268	2189946.224	6035351.482	
2007.00	33 39 53.85658	117 58 47.34959	2189947.91	6035350.08	

References: PMB 314/39-41, RSB 150/1-9, CR 2008-0102, CR 2008-0402, CR 2014-0863

Description:

FD SPIKE AND WASHER STAMPED "LS 5411", FLUSH PER CR 2014-0863 IN LIEU OF 3" CITY OF HUNTINGTON BEACH BRASS DISK, STAMPED "RCE 12589", DOWN 0.92' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF NEWLAND ST. AND INDIANAPOLIS AVE.

