

GPS #: 5026R1

Date Destroyed:

Date Revised: 6/20/2014

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/D-7

City / Location: Huntington Beach

Scale Factor: 0.99997079

Ellipsoid Red. Factor: 1.00000511

Combination Factor: 0.99997589

Convergence Angle: -00 56 27.66017

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 54.16603	117 57 44.78947	2189891.906	6040637.505	
2007.00	33 39 54.18257	117 57 44.80632	2189893.60	6040636.11	

References: MM 253/41-43, RSB 150/1-9. CR 2005-1044, CR 2006-0613, CR 2014-0872

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 5662 FLUSH, IN LIEU OF FD PUNCHED RAILRD. SPIKE, FLUSH. MONUMENT WAS RESET PER CORNER RECORD #2005-1044. STATION IS LOCATED AT CENTERLINE INTER OF BUSHARD ST. AND INDIANAPOLIS AVE.

