

GPS #: 5027

Date Destroyed:

Date Revised: 1/11/2016

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/E-7

City / Location: Huntington Beach

Scale Factor: 0.99997079

Ellipsoid Red. Factor: 1.00000507

Combination Factor: 0.99997586

Convergence Angle: -00 56 10.48953

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 54.34245	117 57 13.54271	2189866.473	6043278.442	-105.945
2007.00	33 39 54.35892	117 57 13.55951	2189868.16	6043277.05	

References: MM 281/36-38, RSB 150/1-9, CR 2003-1258, CR 2015-2541

Description:

FD 2" I.P. WITH BRASS TAG AND TACK IN CONC.,
DOWN 0.92' IN WELL MONUMENT. STATION IS
LOCATED AT CENTERLINE INTER OF BROOKHURST
ST. AND INDIANAPOLIS AVE.

