

GPS #: 5029R1

Date Destroyed:

Date Revised: 3/18/2008

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/D-6

City / Location: Huntington Beach

Scale Factor: 0.99997152

Ellipsoid Red. Factor: 1.00000506

Combination Factor: 0.99997658

Convergence Angle: -00 56 27.85163

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 20.29919	117 57 45.13788	2192533.571	6040651.446	
2007.00	33 40 20.31567	117 57 45.15474	2192535.26	6040650.05	

References: RSB 150/1-9, CR 2007-1789

Description:

FD GEAR SPIKE AND WASHER STAMPED "LS 6970" PER CR 2007-1789. ORIGINAL MONUMENT BEING; 2" I.P. WITH BRASS TAG (NO STAMPING), DOWN 0.9' IN WELL MONUMENT. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF BUSHARD ST. AND ADAMS AVE.

