

GPS #: 5031

Date Destroyed:

Date Revised: 6/10/2008

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/B-6

City / Location: Huntington Beach

Scale Factor: 0.99997152

Ellipsoid Red. Factor: 1.00000509

Combination Factor: 0.99997660

Convergence Angle: -00 57 02.23572

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 19.98064	117 58 47.70933	2192588.669	6035363.490	-106.273
2007.00	33 40 19.99703	117 58 47.72620	2192590.35	6035362.09	

References: RSB 150/1-9, CR 2008-0108, CR 2008-0407

Description:

FD 2" I.P. AND TAG (NO STAMPING), DOWN 0.75' IN WELL MONUMENT WITH A "WATER" LID. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF NEWLAND ST. AND ADAMS AVE.

