

**GPS #:** 5035R2

Date Destroyed:

Date Revised: 10/19/2015

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/G-7

City / Location: Huntington Beach

Scale Factor: 0.99997111

Ellipsoid Red. Factor: 1.00000413

Combination Factor: 0.99997524

Convergence Angle: -00 58 16.33194

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 40 05.77758 | 118 01 02.54798 | 2191344.341   | 6023945.032  |                       |
| 2007.00          | 33 40 05.79406 | 118 01 02.56490 | 2191346.03    | 6023943.63   |                       |

References: MM 681/48-50, RSB 150/1-9, CR 99-003, CR 2001-1172, CR 2001-1253, CR 2002-0668, CR 2015-1528

## Description:

FD PUNCHED SPIKE AND 1 1/2" WASHER STAMPED "CALTRANS" FLUSH IN AC PER CR 2001-1253 IN LIEU OF PUNCHED SPIKE AND WASHER STAMPED "LS 5831" PER CR 99-003. ORIGINAL MONUMENT BEING, FD. CENTERPUNCHED SPIKE. STATION IS LOCATED AT CENTERLINE INTER OF GOLDENWEST ST. AND PACIFIC COAST HWY.

