

GPS #: 5037R1

Date Destroyed:

Date Revised: 9/16/2014

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/H-6

City / Location: Huntington Beach

Scale Factor: 0.99997209

Ellipsoid Red. Factor: 1.00000267

Combination Factor: 0.99997476

Convergence Angle: -00 57 57.06499

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 39.90429	118 00 27.48640	2194743.291	6026966.076	
2007.00	33 40 39.92077	118 00 27.50326	2194744.98	6026964.68	

References: MM 293/33-40, RSB 150/1-9, CR 2013-2039, CR 2013-3362

Description:

FD GEAR SPIKE AND WASHER STAMPED "CITY OF HB", FLUSH PER CR 2013-3362 IN LIEU OF PK NAIL AND LEAD. STATION IS LOCATED AT CENTERLINE INTER OF GOLDEN WEST ST. AND LITTLE HARBOR LN.

