

GPS #: 5039R1

Date Destroyed:
Date Revised: 11/29/2004
Benchmark Designation:
OCS Index Map: 4LB
Page/Grid: 858/A-5
City / Location: Huntington Beach

Scale Factor: 0.99997227
Ellipsoid Red. Factor: 1.00000282
Combination Factor: 0.99997509
Convergence Angle: -00 57 19.54346

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 46.00473	117 59 19.20555	2195263.096	6032745.854	
2007.00	33 40 46.02116	117 59 19.22238	2195264.78	6032744.46	

References: MM 459/48-50, RSB 150/1-9, CR 96-0162

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "CALTRANS", IN LIEU OF PUNCHED SPIKE AND O.C.S. BRASS WASHER, STAMPED "RCE 6978". MONUMENT WAS RESET PER CORNER RECORD #96-0162. STATION IS LOCATED AT CENTERLINE INTER OF BEACH BLVD. AND YORKTOWN AVE.

