

GPS #: 5048

Date Destroyed:

Date Revised: 4/1/2011

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/C-4

City / Location: Huntington Beach

Scale Factor: 0.99997304

Ellipsoid Red. Factor: 1.00000492

Combination Factor: 0.99997796

Convergence Angle: -00 56 45.43077

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 12.31136	117 58 17.12803	2197834.774	6038035.004	-102.838
2007.00	33 41 12.32769	117 58 17.14508	2197836.45	6038033.59	

References: MM 351/30-31, RSB 150/1-9, CR 2010-3408, CR 2011-2067

Description:

FD PUNCHED 2" DISK (NO STAMPING), IN CONC., DOWN 0.95' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF MAGNOLIA ST. AND GARFIELD AVE.

