

GPS #: 5050R1

Date Destroyed:
Date Revised: 11/29/2004
Benchmark Designation:
OCS Index Map: 4LB
Page/Grid: 858/A-4
City / Location: Huntington Beach

Scale Factor: 0.99997304
Ellipsoid Red. Factor: 1.00000268
Combination Factor: 0.99997571
Convergence Angle: -00 57 19.69931

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 12.11900	117 59 19.48919	2197902.766	6032765.907	
2007.00	33 41 12.13541	117 59 19.50615	2197904.45	6032764.50	

References: MM 594/21-22, RSB 150/1-9, CR 96-0165

Description:

FD PUNCHED SPIKE AND WASHER STAMPED "CALTRANS", IN LIEU OF PUNCHED SPIKE AND WASHER, (NO STAMPING). MONUMENT WAS RESET PER CORNER RECORD #96-0165. STATION IS LOCATED AT CENTERLINE INTER OF BEACH BLVD. AND GARFIELD AVE.

