

GPS #: 5053R1

Date Destroyed:

Date Revised: 2/27/2001

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/G-4

City / Location: Huntington Beach

Scale Factor: 0.99997301

Ellipsoid Red. Factor: 1.00000113

Combination Factor: 0.99997414

Convergence Angle: -00 58 11.33596

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 11.21086	118 00 53.45638	2197944.387	6024825.266	
2007.00	33 41 11.22729	118 00 53.47350	2197946.07	6024823.85	

References: CR 914, RSB 150/1-9, CR 2003-1837

Description:

FD 2" I.P. AND TAG STAMPED "LS 3347" IN WELL MONUMENT IN LIEU OF 2" IP WITH CITY OF HUNTINGTON BEACH BRASS TAG STAMPED "RCE 10655" IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 914. STATION IS LOCATED AT CENTERLINE INTER OF EDWARDS ST. AND GARFIELD AVE.

