

GPS #: 5058R1

Date Destroyed:

Date Revised: 6/28/2004

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/G-3

City / Location: Huntington Beach

Scale Factor: 0.99997379

Ellipsoid Red. Factor: 1.00000216

Combination Factor: 0.99997595

Convergence Angle: -00 58 11.54399

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 37.32218	118 00 53.83496	2200583.896	6024837.957	
2007.00	33 41 37.33862	118 00 53.85196	2200585.58	6024836.55	

References: PMB 42/25, RSB 150/1-9, CR 2003-1836

Description:

FD 2" I.P. WITH TAG STAMPED "LS 3347" IN LIEU OF, 2" I.P. WITH CITY OF HUNTINGTON BEACH TAG, (ILLEGIBLE), MONUMENT WAS RESET PER CORNER RECORD 2003-1836. DOWN 0.64' IN WELL MONUMENT. ACCEPTED AS TAG STAMPED "RCE 10655" PER PM 42/25. STATION IS LOCATED AT CENTERLINE INTER OF EDWARDS ST. AND ELLIS AVE.

