

GPS #: 5063

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/C-3

City / Location: Fountain Valley

Scale Factor: 0.99997383

Ellipsoid Red. Factor: 1.00000482

Combination Factor: 0.99997865

Convergence Angle: -00 56 45.66878

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 38.47105	117 58 17.56115	2200479.254	6038042.067	-100.705
2007.00	33 41 38.48739	117 58 17.57813	2200480.93	6038040.66	

References: PMB 71/48, RSB 150/1-9

Description:

FD PUNCHED 3/4" BOLT (HEX BAR) IN CONC., DOWN 1.23' IN WELL MONUMENT. STATION IS LOCATED AT CENTERLINE INTER OF MAGNOLIA ST. AND ELLIS AVE.

