

GPS #: 5066

Date Destroyed:

Date Revised: 5/22/2009

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/F-3

City / Location: Fountain Valley

Scale Factor: 0.99997385

Ellipsoid Red. Factor: 1.00000447

Combination Factor: 0.99997832

Convergence Angle: -00 55 54.14579

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 39.06533	117 56 43.80073	2200409.510	6045964.046	-93.392
2007.00	33 41 39.08162	117 56 43.81770	2200411.18	6045962.64	

References: A/5-10 856, RSB 150/1-9. CR 2005-1208, CR 2006-0409, CR 2008-1567, CR 2008-3273

Description:

FD PUNCHED 3" BRASS DISK IN CONC., NO STAMP, DOWN 1.0' IN WELL W/ 4 CONC. NAIL TIES FLUSH IN AC. STATION IS LOCATED IN THE INTERSECTION OF WARD ST. AND ELLIS AVE.

