

GPS #: 5067

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/E-2

City / Location: Fountain Valley

Scale Factor: 0.99997468

Ellipsoid Red. Factor: 1.00000430

Combination Factor: 0.99997898

Convergence Angle: -00 56 11.55581

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 06.26878	117 57 15.48310	2203202.529	6043332.424	-89.816
2007.00	33 42 06.28508	117 57 15.50017	2203204.20	6043331.01	

References: PMB 198/13-15, RSB 150/1-9

Description:

FD 2" STATE OF CALIFORNIA DIVISION OF HWY.S
BRASS DISK IN CONC., (NO STAMPING), DOWN 1.07'
IN WELL MONUMENT. STATION IS LOCATED AT
CENTERLINE INTER OF BROOKHURST ST. AND
TALBERT AVE.

