

**GPS #:** 5072R1

Date Destroyed:

Date Revised: 10/20/2016

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/J-2

City / Location: Huntington Beach

Scale Factor: 0.99997461

Ellipsoid Red. Factor: 1.00000297

Combination Factor: 0.99997758

Convergence Angle: -00 57 41.68703

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

| Epoch Adjustment | Latitude       | Longitude       | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35          | 33 42 03.92650 | 117 59 59.50194 | 2203195.325   | 6029473.194  |                       |
| 2007.00          | 33 42 03.94293 | 117 59 59.51900 | 2203197.01    | 6029471.78   |                       |

References: PMB 213/19-20, RSB 150/1-9, CR 2005-0695, CR 2005-0944, CR 2016-0197

**Description:**

FD PUNCHED SPIKE AND WASHER STAMPED "LS 5411" PER CR 2005-0944 IN LIEU OF PUNCHED SPIKE AND BRASS WASHER, STAMPED "LS 5346", FLUSH. STATION IS LOCATED AT CENTERLINE INTER OF GOTHARD ST. AND TALBERT AVE.

