

**GPS #:** **5073**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/H-2

City / Location: Huntington Beach

Scale Factor: 0.99997460

Ellipsoid Red. Factor: 1.00000383

Combination Factor: 0.99997844

Convergence Angle: -00 57 54.58316

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 03.75716	118 00 22.97004	2203211.545	6027490.465	-80.102
2007.00	33 42 03.77358	118 00 22.98711	2203213.23	6027489.05	

References: RSB 138/9, RSB 150/1-9

**Description:**

FD "C" NAIL IN A.C.; MONUMENT HAS BEEN RESET WITH A 2 1/2" PUNCHED O.C.S. BRASS DISK STAMPED "7-92", DOWN 1.1', IN A O.C.S. WELL MONUMENT PER RS 138/9. STATION IS LOCATED AT CENTERLINE INTER OF TALBERT AVE. AND GOLDEN WEST ST.

