

GPS #: 5074R1

Date Destroyed:

Date Revised: 2/25/2013

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/G-3

City / Location: Huntington Beach

Scale Factor: 0.99997440

Ellipsoid Red. Factor: 1.00000540

Combination Factor: 0.99997980

Convergence Angle: -00 58 11.69928

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 41 57.05755	118 00 54.11757	2202578.879	6024847.852	
2007.00	33 41 57.07396	118 00 54.13460	2202580.56	6024846.44	

References: RSB 150/1-9, CR 2011-2029, CR 2012-1214

Description:

FD GEAR SPIKE STAMPED "CITY OF HB" PER CR 2012-1214, IN LIEU OF PK NAIL, FLUSH. STATION IS LOCATED AT APPARENT CENTERLINE INTER OF EDWARDS ST. AND INLET DR.

