

GPS #: 5079

Date Destroyed:
Date Revised: 9/9/2010
Benchmark Designation:
OCS Index Map: 4LB
Page/Grid: 857/E-2
City / Location: Huntington Beach

Scale Factor: 0.99997540
Ellipsoid Red. Factor: 1.00000556
Combination Factor: 0.99998096
Convergence Angle: -00 58 46.31530

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 29.28875	118 01 57.11101	2205926.897	6019582.147	-116.086
2007.00	33 42 29.30516	118 01 57.12814	2205928.58	6019580.73	

References: MM 382/7-10, RSB 150/1-9, CR 2010-1415, CR 2010-1927

Description:

FD 2 1/2" ALUMINUM DISK IN CONC., (ILLEGIBLE), DOWN 1.47' IN WELL MONUMENT. ACCEPTED AS 2 1/2" ALUMINUM O.C.S. CAP STAMPED "6/75" PER MM 382/7-10. STATION IS LOCATED AT CENTERLINE INTER OF GRAHAM ST. AND SLATER AVE.

