

GPS #: 5083

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 857/J-1

City / Location: Huntington Beach

Scale Factor: 0.99997543

Ellipsoid Red. Factor: 1.00000381

Combination Factor: 0.99997924

Convergence Angle: -00 57 41.88887

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 30.04647	117 59 59.86924	2205835.706	6029486.478	-79.655
2007.00	33 42 30.06291	117 59 59.88623	2205837.39	6029485.07	

References: MM 341/13-14, RSB 150/1-9

Description:

FD CITY OF HUNTINGTON BEACH TAG IN CONC., (ILLEGIBLE), 0.93' DOWN IN WELL MONUMENT. ACCEPTED AS 2" I.P. WITH TAG STAMPED "RCE 10655" PER MM 341/13-14. STATION IS LOCATED AT CENTERLINE INTER OF GOTHARD ST. AND SLATER AVE.

