

GPS #: 5084R1

Date Destroyed:

Date Revised: 4/30/2004

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 858/A-1

City / Location: Huntington Beach

Scale Factor: 0.99997544

Ellipsoid Red. Factor: 1.00000420

Combination Factor: 0.99997963

Convergence Angle: -00 57 20.53540

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 30.32771	117 59 21.01066	2205809.204	6032769.217	
2007.00	33 42 30.34405	117 59 21.02764	2205810.88	6032767.81	

References: PMB 143/43, RSB 150/1-9, CR 1314, CR 2004-1390

Description:

FD GEAR SPIKE AND TAG STAMPED "LS 6957" IN LIEU OF SPIKE WITH WASHER, (NO STAMPING), DOWN 0.2'. MONUMENT WAS RESET PER CORNER RECORD # 1314. STATION IS LOCATED AT CENTERLINE INTER OF BEACH BLVD. AND SLATER AVE.

