

GPS #: 5092R1

Date Destroyed:

Date Revised: 11/28/2001

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/H-7

City / Location: Huntington Beach

Scale Factor: 0.99997626

Ellipsoid Red. Factor: 1.00000494

Combination Factor: 0.99998120

Convergence Angle: -00 57 54.98303

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 56.06598	118 00 23.69770	2208499.261	6027518.070	
2007.00	33 42 56.08235	118 00 23.71484	2208500.94	6027516.65	

References: PMB 187/27-29, RSB 150/1-9, CR 2001-1520, CR 2003-1278

Description:

FD GEAR SPIKE AND TAG STAMPED "PLS 5344" IN LIEU OF 2" PIPE WITH OCS BENCHMARK TAG, (NO STAMPING), DOWN 1.2' IN WELL MONUMENT. MONUMENT WAS RESET PER CORNER RECORD # 2001-1520B. STATION IS LOCATED ALONG THE CENTERLINE OF GOLDEN WEST ST., 5.00' N'LY FROM ITS CENTERLINE INTER WITH WARNER AVE.

