

GPS #: 5105R2

Date Destroyed:

Date Revised: 9/20/2016

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/G-6

City / Location: Huntington Beach

Scale Factor: 0.99997710

Ellipsoid Red. Factor: 1.00000486

Combination Factor: 0.99998196

Convergence Angle: -00 58 12.37319

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 21.92622	118 00 55.34394	2211158.019	6024889.495	
2007.00	33 43 21.94260	118 00 55.36102	2211159.70	6024888.08	

References: MM 181/12-14, RSB 150/1-9, CR 2001-1507, CR 2004-1804, CR 2005-0821, CR 2006-0614, CR 2006-1786, CR 2016-0635

Description:

FD PK NAIL TAGGED ""LS 5411"" IN LIEU OF GEAR SPIKE AND TAG STAMPED "PLS 5344". MONUMENT HAS BEEN RESET TWICE, ONCE PER CORNER RECORD # 2001-1507 AND ONCE AGAIN PER CORNER RECORD 2005-0821. STATION IS LOCATED AT CENTERLINE INTERSECTION OF EDWARDS ST. AND HEIL AVE.

