

GPS #: 5107R1

Date Destroyed:

Date Revised: 2/25/2013

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 827/J-6

City / Location: Huntington Beach

Scale Factor: 0.99997711

Ellipsoid Red. Factor: 1.00000469

Combination Factor: 0.99998180

Convergence Angle: -00 57 42.28323

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 22.30638	118 00 00.58688	2211118.475	6029514.526	
2007.00	33 43 22.32273	118 00 00.60398	2211120.15	6029513.11	

References: MM 480/2-3, RSB 150/1-9, CR 2011-0529, CR 2012-1749

Description:

FD 2" BRASS DISK STAMPED "RCE 27743", DOWN 0.85' IN WELL, PER CR 2012-1749, IN LIEU OF PUNCHED SPIKE AND WASHER (ILLEGIBLE), DOWN 0.25', ACCEPTED AS WASHER STAMPED "RCE 20801" PER MM 480/2-3. STATION IS LOCATED AT CENTERLINE INTER OF GOTHARD ST. AND HEIL AVE.

