

GPS #: 5109

Date Destroyed:
Date Revised: 6/2/2004
Benchmark Designation:
OCS Index Map: 4LB
Page/Grid: 828/B-6
City / Location: Westminster

Scale Factor: 0.99997713
Ellipsoid Red. Factor: 1.00000434
Combination Factor: 0.99998147
Convergence Angle: -00 57 03.65049

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 22.79708	117 58 50.28388	2211068.954	6035452.644	-90.718
2007.00	33 43 22.81343	117 58 50.30094	2211070.63	6035451.23	

References: A/5-11&12 405, RSB 150/1-9, CR 2004-0349, CR 2004-0978,

Description:

FD 3" ALUMINUM DISK (ILLEGIBLE), IN CONC., DOWN 1.64' IN WELL MONUMENT. ACCEPTED AS 2 1/4" DISK STAMPED "8-76" PER A/5-11&12 405. STATION IS LOCATED AT CENTERLINE INTERSECTION OF NEWLAND ST. AND HEIL AVE.

